

X

इंटरनेट



### Disclosure to Promote the Right To Information

Whereas the Parliament of India has set out to provide a practical regime of right to information for citizens to secure access to information under the control of public authorities, in order to promote transparency and accountability in the working of every public authority, and whereas the attached publication of the Bureau of Indian Standards is of particular interest to the public, particularly disadvantaged communities and those engaged in the pursuit of education and knowledge, the attached public safety standard is made available to promote the timely dissemination of this information in an accurate manner to the public.

"जानने का अधिकार, जीने का अधिकार" Mazdoor Kisan Shakti Sangathan "The Right to Information, The Right to Live"

"पुराने को छोड नये के तरफ" Jawaharlal Nehru "Step Out From the Old to the New"

मानक

IS 2193 (1986): Precast Prestressed Concrete Street

Lighting Poles [CED 53: Cement Matrix Products]



611111111

Made Available By Public.Resource.Org



"ज्ञान से एक नये भारत का निर्माण″ Satyanarayan Gangaram Pitroda "Invent a New India Using Knowledge"

"ज्ञान एक ऐसा खजाना है जो कभी चुराया नहीं जा सकता Bhartrhari-Nītiśatakam "Knowledge is such a treasure which cannot be stolen"



# $\star \star \star \star \star \star \star$ $\star \star \star \star \star \star \star$

## BLANK PAGE



PROTECTED BY COPYRIGHT

## Indian Standard

## SPECIFICATION FOR PRECAST PRESTRESSED CONCRETE STREET LIGHTING POLES

## (First Revision)

UDC 621'315'668'3; 628'971'6



© Copyright 1987 INDIAN STANDARDS INSTITUTION MANAK BHAVAN, 9 BAHADUR SHAH ZAFAR MARG NEW DELHI 110002

## Indian Standard

SPECIFICATION FOR PRECAST PRESTRESSED CONCRETE STREET LIGHTING POLES

## (First Revision)

Cement and Concrete Sectional Committee, BDC 2			
Chairman	Representing		
DR H. C. VISVESVARAYA	National Council for Cement and Building Materials, New Delhi		
Members			
ADDITIONAL DIRECTOR STANDARDS ( B & S ) DEPUTY DIRECTOR STANDARDS ( B & S ) ( Alternate )	Research, Designs and Standards Organization (Ministry of Railways), Lucknow		
SHRI K. P. BANERJEE	Larsen and Toubro Limited, Bombay		
SHRI HARISH N. MALANI ( Alter	nate)		
SHRI S. K. BANERJEE SHRI R. V. CHALAPATHI RAO SHRI S. ROY ( <i>Alternate</i> )	Geological Survey of India, Calcutta		
CHIEF ENGINEER (BD)	Bhakra Beas Management Board, Nangal Township		
SHRI J. C. BASUR (Alternate) CHIEF ENGINEER (DESIGNS) EXECUTIVE ENGINEER (D)-III ( CHIEF ENGINEER (RESEARCH-CUM- DIRECTOR)	Central Public Works Department, New Delhi Alternate) Irrigation Department, Government of Punjab		
RESEARCH OFFICER (CONCRETE			
DIRECTOR	A. P. Engineering Research Laboratories, Hyderabad		
JOINT DIRECTOR ( Alternate ) DIRECTOR	Central Soil and Materials Research Station, New Delhi		
CHIEF RESEARCH OFFICER ( Alta DIRECTOR ( C & MDD-I ) DEPUTY DIRECTOR ( C & MDD	ernate) Central Water Commission, New Delhi I-I) (Alternate)		
SHRI V. K. GHANEKAR	Structural Engineering Research Centre (CSIR), Roorkee		
	(Continued on page 2)		

#### © Copyright 1987

#### INDIAN STANDARDS INSTITUTION

This publication is protected under the *Indian Copyright Act* (XIV of 1957) and reproduction in whole or in part by any means except with written permission of the publisher shall be deemed to be an infringement of copyright under the said Act.

(Continued from page 1)	
Members	Representing
Shri A. V. Gokak	Development Commissioner for Cement Industry (Ministry of Industry)
SHRI S. S. MIGLANI ( Alternate )	
SHRI S. GOPINATH SHRI T. TAMILAKARAN ( Alternat	The India Cements Limited, Madras te)
-Shri S. K. Guha Thakurta Shri S. P. Sankarnarayanan (	Gannon Dunkerley and Co Ltd, Bombay Alternate)
SHRI A. K. GUPTA	Hyderabad Industries Limited, Hyderabad
SHRI P. J. JAGUS	Bombay
DR A. K. CHATTERJEE (Alternat	e) Indian Hume Pine Co Limited Bombay
SHRI R. L. KAPOOR	Roads Wing, Ministry of Transport
SHRI K. K. LAHA SHRI S. K. LAHA	The Institution of Engineers (India), Calcutta
Dr Mohan Rai	Central Building Research Institute (CSIR), Roorkee
DR S. S. REHSI ( Alternate ) DR A. K. MULLICK	National Council for Cement and Building Materials New Delhi
Shri K. K. Nambiar	In personal capacity ('Ramanalaya', 11 First Crescent Park Road, Gandhinagar, Adyar, Madras)
Shri S. N. Pal	M. N. Dastur and Company Private Limited, Calcutta
SHRI BIMAN DASGUPTA ( Alterna	ate)
Shri H. S. Pasricha Shri Y. R. Phull	Industan Pretao Limited, New Deini Indian Roads Congress, New Delhi; and Central Road Research Institute (CSIR), New Delhi
SHRI M. R. CHATTERJEE (Alternate)	Central Road Research Institute (CSIR), New Delhi
DR M. RAMAIAH	Structural Engineering Research Centre (CSIR), Madras
Assistant Director ( Alternat	e) Delmis Compart ( Discust ) Limited New Delhi
SHRI A. V. RAMANA DR K. C. NARANG (Alternate)	Daimia Cement (Bharat) Limited, New Deimi
SHRI G, RAMDAS	New Delhi
DR A. V. R. RAO	National Buildings Organization, New Delhi
SHRI J. SEN GOFTA (Alternate SHRI T. N. SUBBA RAO SUBLE A PEDDI (Alternate)	Gammon India Limited, Bombay
SHRI S. A. RIDDI (Anternate) SHRI A. U. RIJHSINGHANI	Cement Corporation of India, New Delhi
SHRI H. S. SATYANARAYANA	'Engineer-in-Chief's Branch, Army Head-
SHRI V. R. KOTNIS ( Alternate	)
SECRETARY	Central Board of Irrigation and Power, New Delhi
SHRI K. R. SAXENA ( Alternate	?)

(Continued on page 15)

n an an an Arrange. Search an Arrange an Ar

### Indian Standard

#### SPECIFICATION FOR PRECAST PRESTRESSED CONCRETE STREET LIGHTING POLES

### (First Revision)

#### 0. FOREWORD

**0.1** This Indian Standard (First Revision) was adopted by the Indian Standards Institution on 29 August 1986, after the draft finalized by the Cement and Concrete Sectional Committee had been approved by the Civil Engineering Division Council.

**0.2** This standard has been prepared with the object of providing guidance to the manufacturers and users in obtaining precast prestressed concrete street lighting poles capable of giving satisfactory service. This standard covers only poles in the manufacture of which prestressing system and mechanical compacting methods, such as, vibration, shocking, etc, have been adopted. It does not cover hand compacted poles. Recommendations regarding selection, handling and erection of poles are covered in IS : 7321-1974\*.

**0.3** This standard was first published in 1962 under the title 'Specification for prestressed concrete street lighting columns'. This modification in title is intended to make it more clear.

0.4 The present revision has been taken up with a view to incorporating the modifications found necessary in the light of experience gained during the use of this standard. This revision incorporates significant modifications in respect of materials, design, tests for poles and brackets, and earthing of poles. In addition, modifications have been made in respect of some other provisions, such as, length, outreach, cover of concrete, tolerance on dimensions, sampling and inspection, marking, etc.

0.5 For the purpose of deciding whether a particular requirement of this standard is complied with, the final value, observed or calculated, expressing the result of a test or analysis, shall be rounded off in accordance with IS: 2-1960<sup>†</sup>. The number of significant places retained in

<sup>\*</sup>Code of practice for selection, handling and erection of concrete poles for overhead power and telecommunication lines.

<sup>†</sup>Rules for rounding off numerical values ( revised ).

#### IS: 2193 - 1986

the rounded off value should be the same as that of the specified value in this standard.

#### 1. SCOPE

1.1 This standard covers the requirements for precast prestressed concrete poles suitable for use in street lighting. It also covers prestressed concrete street lighting poles where untensioned longitudinal reinforcement is used to act in conjunction with tensioned steel under load.

1.2 Concrete fittings attached to or forming part of a pole are also covered by this standard, as far as practicable.

1.3 The poles covered by this standard are not intended for overhead wiring purposes.

#### 2. TERMINOLOGY

2.0 For the purpose of this standard, the following definitions shall apply.

2.1 Load Factor — The ratio of ultimate transverse load to the transverse load at first crack. For design, the transverse load at first crack shall be taken as not less than the value of the working load.

2.2 Maximum Working Load — The miximum working load in the transverse direction that is ever likely to occur including the wind pressure on the pole. This load is assumed to act at a point 600 mm below the connection of the bracket to the pole and will create a bending moment equal to the sum of the bending moments caused by the following loads:

- a) Wind pressure on the pole, bracket, luminaire and any raising or lowering contact gear;
- b) Overhanging weight of bracket and luminaire; and
- c) If raising and lowering gear is provided, the weight of such gear attached to the bracket plus 50 percent of the weight of the luminaire and the moving part of gear.

**2.3 Mounting Height** — The mounting height is the vertical distance from the centre of the light source to the road surface or to the horizontal plane through the nearest point of the road where the light source is not vertically above it.

2.4 Outreach — The outreach is the shortest distance between the vertical through the centre of the base of the pole and the vertical through the centre of light source.

4

2.5 Side Entry Luminaire — A luminaire in which the lead is taken through its side.

2.6 Top Entry Luminaire — A luminaire in which the lead is taken through the top.

2.7 Ultimate Failure — The conditions existing when the pole ceases to sustain a load increment owing to either crushing of concrete, or snapping of the prestressing tendon or permanent stretching of the steel in any part of the pole.

2.8 Ultimate Transverse Load — The load at which failure occurs when it is applied to a point 600 mm below the centre of light source and perpendicular to the axis of the pole along the transverse direction with the butt end of the pole planted to the required depth as intended in the design.

#### 3. OVERALL LENGTH OF POLES

3.1 The minimum length of pole shall be arrived at after fixing the mounting height on the basis of the traffic situation of the concerned street and adding thereto the minimum planting depth as mentioned in 5.3. However, in no case, the pole length should be less than 5'2 m, considering the minimum mounting height of 4'0 m and the corresponding planting depth of 1'2 m. For longer poles, the lengths shall be in steps of 0'5 m.

3.2 Tolerances — The tolerances on overall length of poles shall be  $\pm 15$  mm. The tolerance on cross-sectional dimensions shall be  $\frac{+5}{-3}$  mm.

The tolerance on uprightness of the pole shall be 0'5 percent.

#### 4. MATERIALS

#### IS: 1489-1976<sup>‡</sup>, or IS: 8041-1978<sup>§</sup>, or IS: 8043-1978<sup>¶</sup>, or IS: 8112-1976<sup>¶</sup>.

4.2 Aggregates — Aggregates shall comply with the requirements of IS: 383-1970\*\*. Where specified, sample of aggregate shall be submitted to the purchaser for approval. The miximum size of aggregates shall in no case exceed 20 mm.

<sup>\*</sup>Specification for ordinary and low heat Portland cement ( third revision ).

Specification for Portland slag cement ( third revision ).

<sup>\$\$</sup>pecification for Portland-pozzolana cement ( second revision ).

Specification for rapid hardening Portland cement (first revision).

Specification for hydrophobic Portland cement (first revision).

Specification for high strength ordinary Portland cement.

<sup>\*\*</sup>Specification for course and fine aggregates from natural sources for concrete (second revision).

4.3 Reinforcement - Reinforcing bars and wires used for the manufacturing of prestressed concrete poles shall conform to the following:

- a) IS: 432 (Part 1)-1982 Specification for mild steel and medium tensile steel bars and hard-drawn steel wire for concrete reinforcement: Part 1 Mild steel and medium tensile steel bars (third revision).
- b) IS: 432 (Part 2)-1982 Specification for mild steel and medium tensile steel bars and hard-drawn steel wire for concrete reinforcement: Part 2 Hard-drawn steel wire (*third revision*).
- c) IS: 1785 (Part 1)-1983 Specification for plain hard-drawn steel wire for prestressed concrete: Part I Cold drawn stress-relieved wire (second revision).
- d) IS: 1785 (Part 2)-1983 Specification for plain hard-drawn steel wire for prestressed concrete: Part 2 As-drawn wire (first revision).
- e) IS: 2090-1983 Specification for high tensile steel bars used in prestressed concrete (first revision).
- f) IS: 6003-1983 Specification for indented wire for prestressed concrete (first revision).
- g) IS: 6006-1983 Specification for uncoated stress relieved strand for prestressed concrete (first revision).

**4.3.1** The diameter of plain wire used for pretensioning system, where prestress is developed by bond, shall not exceed 5 mm, as far as possible.

**4.3.2** The surface of all reinforcement shall be free from loose scales, oil, grease, clay or other material that may have deteriorating effect on the bond between reinforcement and concrete. Slight rust may, however, be permissible.

4.4 Concrete — The concrete shall conform to the requirements laid down in IS: 1343-1980\* for prestressed concrete members and IS:456-1978<sup>†</sup> for reinforced concrete member, such as concrete fittings.

4.5 Admixtures — Admixtures may be used with the approval of the purchaser. However, use of any admixture containing chlorides in any form is prohibited.

4.5.1 The admixture shall conform to IS : 9103-1979<sup>‡</sup>.

<sup>\*</sup>Code of practice for prestressed concrete (first revision).

<sup>&</sup>lt;sup>†</sup>Code of practice for plain and reinforced concrete ( third revision ). tSpecification for admixtures for concrete.

#### 5. DESIGN

5.1 The poles shall be so designed that they do not fail owing to failure initiated by compression of concrete.

5.2 The maximum wind pressure to be assumed for computing the design transverse load at first crack shall be as specified by the State Governments, who are empowered in this behalf under the Indian Electricity Rules, 1956. In the absence of any data/information from the State Governments, wind pressure may be determined as specified in IS: 875-1964\*. The wind pressure may also be calculated considering the shape factor of poles and brackets depending on their plan shape as per IS: 875-1964\*.

5.3 Depth of Planting — The minimum depth of planting of a pole below ground level shall be in accordance with Table 1, the actual depth being determined on the basis of ground conditions.

TABLE 1         MINIMUM DEPTH OF PLANTING OF PRESTRESSED           CONCRETE POLES IN THE GROUND				
Mounting Height, m	MINIMUM DEPTH IN GROUND, M	Remarks		
(1)	(2)	(3)		
4·0 to 6 0 6·5 to 7·5 8·0 to 9 0	1·20 1·50 } 1·80 J	In increments of preferably 0.5 m		

5.4 Unless otherwise specified by the purchaser, the distance from the luminaire support to the centre of light source shall be taken as given in Table 2.

SL No.	Mounting Height of Poles, m	Nominal Distance From the Luminaire Support to the Centre of Light Source, mm		
(1)	(2)	For Top Entry Luminaire (3)	For Side Entry Luminaire (4)	
i) ii) iii)	4 0 to 5 5 6 0 to 7 5 7 5 to 9 0	300 300 to 450* 450	100 100 to 150* 150	

\*Code of practice for structural safety of buildings: Loading standards ( revised ).

TABLE 3 STANI	)ARD L	ENGTH OF OUTREACH
MOUNTING HEIGHT, m		OUTREACH
4·5 6·0 7·5 9·0	}	Not exceeding 0.5 m Varying from 0.50 to 2.75 m in steps of 0.25 m

5.5 Outreach — This will be in standard length as specified in Table 3.

5.5.1 Unless otherwise specified by the purchaser, the distance between the vertical through the centre of light source of a side entry luminaire and the extremity of the concrete on the bracket arm shall be taken as 300 mm nominal.

5.6 The poles shall be designed to resist the maximum bending moment due to a load of 90 kg or the maximum working load, whichever is greater, applied at 600 mm below the centre of light source or, if so specified by the purchaser, at a point immediately below the connection of the bracket to the pole.

5.6.1 The load factor on transverse strength for prestressed concrete poles shall not be less than 2.5. This factor may be reduced to a value not less than 2.0 in the case of street lighting poles by the State Governments, who are empowered in this behalf under the Indian Electricity Rules, 1956.

5.7 Vertical Load on Bracket — The vertical load on the bracket shall be taken as equivalent to the weight of the luminaire, weight of raising and lowering gear attached to the bracket (if used) plus 50 percent of the weight of the luminaire and of the moving part of that gear, the load being applied at point of support of the luminaire with the bracket rigidly fixed to the pole in the designed manner.

5.8 Transverse Load on Bracket — The load caused by wind pressure on the luminaire and bracket is considered as acting at the point of support of the luminaire with the bracket fixed to the pole. The design of the connections of bracket to pole shall provide for torsional stresses due to wind load on the bracket and the luminaire.

#### 6. FITTINGS

6.1 Spigot — When poles with top spigots are required, and unless otherwise specified by the purchaser, the following sizes shall be provided:

- a) For 6, 7.5 and 9 m mounting : A spigot with 100 mm dia and heights 150 mm long
- b) For 4.5 m mounting height
- : A spigot with 80 mm dia and 80 mm long

1. Star 1. Star

6.2 Nipples — Unless otherwise specified by the purchaser, nipples shall be provided at the end of the bracket as follows:

- a) For mounting heights 7.5 and 9 m:
  - i) To Take Pendant Lumincire Vertical 30 mm gas nipple having at least 40 mm of exposed thread; and
  - ii) To Take Side Entry Luminaire 30 mm steel tubing with end horizontal and plain or threaded, as specified by the purchaser.
- b) For mounting heights 4.5 and 6 m:
  - i) To Take Pendant Luminaire Vertical 20 or 30 mm gas nipple having at least 25 mm of exposed thread; and
  - ii) To Take Side Entry Luminaire 20 or 30 mm steel tubing with end horizontal and plain or threaded, as specified by the purchaser.

6.3 Ladder Arms — If required, and unless otherwise specified, ladder arms shall be as follows:

- a) Single arm, of 550 mm overall projection, and
- b) Double arms, each of 250 mm overall projections.

**6.4 Door and Door Openings** — Unless otherwise specified by the purchaser, a weatherproof door with a locking device, which will resist unauthorized entry, shall be included in the pole. The door opening shall be of size agreed upon between the manufacturer and the purchaser.

6.4.1 The bottom of the opening shall be at least 300 mm above ground level.

6.5 All metal works shall be of non-corroding metal or of metal suitably protected against corrosion.

**6.6 Bore** — All poles shall have a smooth walled central duct of diameter not less than 30 mm for the purpose of taking the supply from the base to the lighting unit at top.

6.7 Service Connections — Suitable apertures shall be provided on at least two sides of the pole below ground level for the entry of electric cables or gas service pipes. Unless otherwise specified, service slots shall be approximately 225 mm long and 75 mm wide with the top at least 300 mm below ground level. The edges of the slot shall be suitably rounded to prevent damage to the sheath or armouring of the cables.

**6.8 Breathing Holes** — Breathing holes shall be provided in the door and also as close to the top of the pole as is practicable to allow circulation of air and to limit condensation. The holes shall be suitably protected against the entry of rain water.

#### 7. MANUFACTURE

7.1 All reinforcement and ducts shall be accurately placed and maintained in position during manufacture. Grouping of high tensile wires may be permitted as long as the diameter of the wire is between 3 and 5 mm.

7.2 For prestressed pretensioned system, all wires shall be accurately stretched with uniform prestress in each wire. Each wire or group of wires shall be anchored positively during casting. Care shall be taken to see that the anchorages do not yield before the concrete attains the necessary strength.

7.3 For post-tensioned poles, the relative positions of wires in a cable, whether curved or straight, shall be accurately maintained by suitable means to ensure the free flow of grout.

7.4 Cover — For pretensioned system, the cover of concrete measured from the outside of the prestressing tendon shall be at least 20 mm. Where cables and large sized bars are used, the clear cover shall be at least 30 mm. The minimum clear distance between single wires in pretensioned system shall be the greater of the following:

a) One- and one-third times the largest size of aggregate used, and

b) Three times the diameter of the wire.

The clear distance between cables or large bars shall not be less than 40 mm or 6.5 mm in excess of the largest size aggregate used, whichever is greater.

7.5 Welding and Lapping of Steel — The high tensile steel wire or bar shall be continuous over the entire length of the tendon. Welding shall not be allowed in any case. Jointing or coupling in the case of bars and indented or crimped wires may be permitted provided the strength of joint or coupling is not less than the strength of each individual bar or wire.

7.6 Compacting — Concrete shall be compacted by spinning, vibrating, shocking or other suitable mechanical means. Hand compaction shall not be permitted.

7.7 Curing — The concrete shall be covered with a layer of sacking, canvas, hessian or similar absorbent material and kept constantly wet up to the time when the strength of concrete is at least equal to the minimum strength of concrete at transfer of prestress in case of poles. In case of reinforced concrete brackets, the concrete shall be cured as mentioned above till the concrete attains sufficient strength. Then the poles and the brackets may be removed from the mould and watered at intervals to prevent surface cracking of the unit; the interval shall

depend on the atmospheric humidity and temperature. Steam curing may also be permitted.

7.8 During manufacture, daily tests on concrete cubes shall be carried out till the concrete achieves required strength at transfer. Thereafter, the tests on concrete shall be carried out as detailed in IS : 1343-1980\*. The manufacturer shall apply, when required by the purchaser or his representative, results of compressive tests conducted in accordance with IS : 456-1978† on concrete cubes made from the concrete used for the poles. If the purchaser so desires, the manufacturer shall supply cubes for test purposes and such cubes shall be tested in accordance with IS : 456-1978†.

7.9 Earthing — Earthing shall be provided by either of the following means:

- a) By having a length of galvanized iron wire of 4 mm diameter or equivalent strip or equivalent bare copper cable embedded in concrete during manufacture and the ends of the wire or strip or cable left projecting from the pole to a length of 100 mm at 215 mm from top and 150 mm below ground level.
- b) By providing two holes of suitable dimensions, 215 mm from top and 150 mm below ground level to enable a galvanized iron wire of 4 mm diameter or equivalent strip or equivalent bare copper cable to be taken from the top hole to the bottom hole through the central hollow.

 $N_{OTE}$  — The details of embedment of wire or strip or cable shall be as agreed upon between the manufacturer and the purchaser.

7.10 Finish — The poles shall be of good finish and free from honeycombing. The surfaces of the poles in contact with the moulds shall be smooth and regular in shape. All arrises shall be clear and well-defined so as to present a neat appearance.

#### 8. TESTS

8.1 Transverse Strength Test for Poles — The transverse strength test of poles shall be conducted in accordance with IS: 2905-1966<sup>‡</sup>. A prestressed concrete pole shall be deemed not to have passed the test if cracks wider than 0<sup>1</sup> mm appear at a stage prior to the application of the design transverse load at first crack and/or the observed ultimate transverse load is less than the design ultimate transverse load.

<sup>\*</sup>Code of practice for prestressed concrete (first revision).

<sup>†</sup>Code of practice for plain and reinforced concrete ( third revision ).

Methods of test for concrete poles for overhead power and telecommunication lines.

#### 8.2 Strength Tests for Brackets

**8.2.1** The brackets shall be tested either in its normal position at the top of the pole or fixed into a special pole head of identical dimensions, which may be a portion cut from a pole. The pole or pole head shall be rigidly fixed in a vertical position.

**8.2.2** Vertical and transverse test loads calculated in accordance with 5.7 and 5.8 shall be gradually applied at the end of the bracket, the ratio between the vertical and transverse loads being kept constant. When the maximum working loads are reached, it shall be maintained for at least 2 minutes and the maximum deflection shall be measured.

**8.2.3** The load shall then be reduced to zero and the residual deflection shall be measured after 10 minutes.

**8.2.4** The bracket shall be considered satisfactory, if the recovery is at least 75 percent of the maximum deflection while under load.

**8.2.5** The load causing failure shall not be less than 'the maximum working load multiplied by the load factor considered in the design'.

#### 9. SAMPLING AND INSPECTION

#### 9.1 Scale of Sampling

9.1.1 Lot — In a consignment, 500 poles (or brackets) or a part thereof of the same mounting height, same dimensions and belonging to the same batch of manufacture, shall be grouped together to constitute a lot.

9.1.2 For ascertaining the conformity of the material in the lot to the requirements of this specification, samples shall be tested from each lot separately.

9.1.3 The number of poles or brackets to be selected from the lot shall depend on the size of the lot and shall be according to Table 4.

TABLE 4 SCALE OF SAMPLING AND PERMISSIBLE NUMBEROF DEFECTIVES				
No. of Poles or Brackets in the Lot	DIMENSIONAL REQUIREMENTS		TRANS-	TRANS-
	Sample Size	Acceptance Number	verse Strength at First Crack	VERSE STRENGTH ULTIMATE
(1)	(2)	(3)	(4)	(5)
Up to 100	10	1	2	Nil
101 to 200	15	1	3	Nil
201 to 300	20	2	4	Nil
301 to 500	30	3	5	1
Note — h' provided the	Te poles or bra crack is closed a	ickets tested up after removal of	to first cracl the load.	k may be used

#### 9.2 Number of Tests and Criteria for Conformity

9.2.1 All the poles/brackets selected according to 9.1.3 shall be tested for overall length, cross-section and uprightness (see 3.2). A pole/ bracket failing to satisfy one or more of these requirements shall be considered as defective. All the poles/brackets in the lot shall be considered as conforming to these requirements if the number of defective poles/brackets found in the sample is less than or equal to the corresponding acceptance number given in col 3 of Table 4.

9.2.2 The lot having been found satisfactory according to 9.2.1 shall be further tested for transverse strength (see 8.1) of the poles. For this purpose, the number of poles given in col 4 of Table 4 shall be tested. These poles may be selected from those already tested according to 9.2.1 and found satisfactory. All these poles tested for transverse strength shall satisfy the corresponding specification requirements. If one or more poles fail, twice the number of poles originally tested shall be selected from those already selected and subjected to this test. If there is no failure among these poles, the lot shall be considered to have satisfied the requirements of this test.

9.2.3 All the brackets selected from the lot according to 9.1.3 shall be subjected to strength test for brackets (see 8.2). All the brackets tested for strength test shall satisfy the requirements of this specification. If one or two brackets fail, twice the number of brackets originally tested shall be selected from the lot and subjected to this test. If there is no failure among these brackets, the lot shall be considered to have satisfied the requirements of the specification. If more than two brackets fail, the lot shall be considered not to have satisfied the requirements of the specification.

#### 10. MARKING

10.1 The poles shall be clearly and indelibly marked with the following particulars either during or after the manufacture, but before testing, at a position so as to be clearly read after erection in position:

- a) Month and year of manufacture;
- b) Name of manufacturer or his registered trade-mark or both;
- c) Serial number of poles; and
- d) Position of centre of gravity of the poles with the word 'C.G.'.

10.2 Each pole may also be marked with the ISI Certification Mark.

NOTE — The use of the ISI Certification Mark is governed by the provisions of the Indian Standards Institution (Certification Marks) Act and the Rules and Regulations made thereunder. The ISI Mark on products covered by an Indian

Standard conveys the assurance that they have been produced to comply with the requirements of that standard under a well-defined system of inspection, testing and quality control which is devised and supervised by ISI and operated by the producer. ISI marked products are also continuously checked by ISI for conformity to that standard as a further safeguard. Details of conditions under which a licence for the use of the ISI Certification Mark may be granted to manufacturers or processors, may be obtained from the Indian Standards Institution.

## **11. INFORMATION TO BE SUPPLIED WITH THE ENQUIRY OR ORDER**

11.1 The following information shall be supplied with enquiry or order:

- a) Mounting height;
- b) Type of luminaire and outreach;
- c) Weight of luminaire and, if provided, weight of raising and lowering gear;
- d) Spigot and nipples (see 6.1 and 6.2);
- e) Angle which the axis of the nipple at the end of the bracket makes with the vertical (see 6.2);
- f) Ladder arms, if required (see 6.3);
- g) Any special requirements in respect of depth of planting;
- h) Size of door opening (see 6.4); and
- i) Position and size of service slots (see 6.7).

Head-

 Members
 Representing

 SUPERINTENDING ENGINEER
 Public Works Department, Government of Tamil Nadu

 EXECUTIVE ENGINEER (SMD)
 (DIVISION) (Alternate)

 SHRI L. SWAROOP
 Orissa Cement Limited, New Delhi

 SHRI H. BHATTACHARYYA (Alternate)
 Director General, ISI (Ex-officio Member)

 Director (Civ Engg)
 Science

Secretary SHRI N. C. BANDYOPADHYAY Deputy Director ( Civ Engg ), ISI

#### Concrete Poles Subcommittee, BDC 2:12

#### Convener

(Continued from page 2)

National Council for Cement and Fuilding DR N. RAGHAVENDRA Materials, New Delhi Members SHRI J. L. BANDYOPADHYAY Indian Posts and Telegraph Department. Jabalpur SHRI V. V. SURYA RAO ( Alternate ) SHRI S. N. BASU Directorate General of Supplies and Disposals. New Delhi SHRI T. N. OBOVEJA ( Alternate ) SHRI R. S. BHATIA Punjab State Electricity Board, Patiala SHRI S. K. SHARMA ( Alternate ) SHRI P. C. CHATTERJEE SHRI U. N. RATH (Alternate) Orissa Cement Ltd, Rajgangpur DIRECTOR (RE) Central Electricity Authority, Rural Electrification Directorate, New Delhi DEPUTY DIRECTOR ( RE ) ( Alternate ) SHRI G. L. DUA Rural Electrification Corporation Ltd, New

Delhi SHRI S. K. SETHI (*Alternate*) SHRI P. C. JAIN Engineer-in-Chief's Branch, Army quarters, New Delhi

SHRI SUCHA SINGH ( Alternate ) JOINT DIRECTOR STANDARDS Research, Designs and Standards Organization (B&S)CB-II (Ministry of Railways), Lucknow Assistant Director (E) ( B & S )-I ( Alternate ) Shri N. G. Joshi The Indian Hume Pipe Co Ltd, Bombay SHRI R. SAMPAT KUMARAM Delhi Electric Supply Undertaking, New Delhi SHRI RAMESH CHANDER ( Alternate ) SHRI A. V. TALATI Steelpipe and Fabrication Works. The Vadodara SHRI H. C. SHAH ( Alternate ) SHRI T. G. TEPAM Maharashtra State Electricity Board, Bombay SHRI R. B. JOSHI (Alternate)